



City of
GREENFIELD, MASSACHUSETTS

DEPARTMENT OF PUBLIC WORKS

William F. Martin
Mayor

City Hall • 14 Court Square • Greenfield, MA 01301
Phone 413-772-1528 • Fax 413-773-9593
DPW@greenfield-ma.gov • www.greenfield-ma.gov

**Bank Row Sidewalk Improvement Project
Contract DPW 19-08
Addendum #1**

September 13, 2018

The following questions have been received:

1) For the replacement of the frame and grate to frame and cover, is that going to be an accessible cover that will be hinged or if the hole below can be filled can it be abandoned and concrete sidewalk poured in its place?

Answer:

The new frame and cover shall not be an accessible cover that is hinged. It shall be bolted in place and not be abandoned.

2) Do you have any specs on the frame and grate that you would want? Can it be aluminum hatch doors or does it have to be steel?

Answer:

There are no specifications on the replacement frame and cover or on the replacement frame and hatch doors. The existing dimensions shall be matched. Both of these shall be steel and not aluminum.

3) Do we need to provide access to the stairway at all times or is there another way into the building serviced by the stairway?

Answer:

Access to the stairway does not have to be provided at all times but should be maintained to the maximum extent possible. There is another way into the building at the lower level.

4) I am assuming that for the curb cut we would be removing and resetting the existing granite curb or will you want new granite curb?

Answer:

The existing granite curb shall be removed and reset. This work is a part of Item 5.